

**NOTICE TO CONTRACTORS
HIGHWAY CONSTRUCTION****November 13, 2017**

Bidding proposals may not be issued to bidders unless they are prequalified, except where otherwise provided in Plans and Specifications. For those contractors who are not prequalified, application for prequalification will be submitted on DOT Form 420-010 (Standard Questionnaire and Financial Statement) and must be received by the Prequalification Engineer no less than fifteen days prior to the scheduled bid opening to receive consideration for issuance of a bidding proposal for that bid opening. Informational copies of plans and specifications are on file in the office of the County Engineer of the County in which the work is situated, the chapter offices of the Associated General Contractors of America, the offices of the Regional Administrators or the Headquarters of the Department of Transportation, and at www.wsdot.wa.gov/biz/contaa/ where they may be inspected. The use of informational proposals shall be allowed only upon written request and will be accepted only when written authority for their use has been granted. **ESTIMATE RANGES PUBLISHED IN THIS NOTICE MUST NOT BE USED AS A BASIS FOR BID PREPARATION.**

All bid proposals shall be accompanied by a bid proposal deposit in cash, certified check, cashier's check or surety bond in an amount equal to five percent (5%) of the amount of such bid proposal. Should the successful bidder fail to enter into a contract and furnish a satisfactory performance bond, the bid proposal deposit shall be forfeited. **Bonds submitted on other than the bond form provided by the department may be subject to rejection. The right is reserved to reject any and all bids and to waive informalities in the bidding.** Sealed bids will be received in the Bid Room 2D20, located on the second floor of the Department of Transportation, 310 Maple Park Avenue SE, Olympia, Washington, 98501 until 11:00:59 am Pacific Time, or at P.O. Box 47360, Olympia, Washington, 98504-7360, until 11:00:59 am Pacific Time or electronically via BidX.com until 11:00:59 am Pacific Time, on the dates shown below except where otherwise provided in the Plans and Specifications.

FEE: Project Documents will be furnished for the non-refundable fee Plus Sales Tax of:

| | | |
|-------------------------------------|--|------------------------------------|
| Electronic – plans only \$10 | Electronic – with proposal \$15 | |
| Paper – one volume \$35 | Paper – two volumes \$50 | Paper – three volumes \$100 |

(Remittance may be made to the Department of Transportation Cash Receipts, Transportation Building, and P.O. Box 47305, Olympia, WA 98504-7305) TO ORDER PLANS AND SPECIFICATIONS PLEASE CALL (360) 705-7835. To order by e-mail, the address is: CAA@wsdot.wa.gov.

Electronic Project Plans, Specifications, Geotechnical Reports, Addenda, Planholders Lists, Award/Bid Results, and Bid Tabulations are available on the Internet at: <http://www.wsdot.wa.gov/biz/contaa>

SMALL WORKS ROSTER: The Department of Transportation is soliciting contractors interested in qualifying for placement on the department's Small Works Roster. The small works roster process as authorized by RCW 39.04.155 and WAC 468-15 may be used to secure bids for the Agency's small works projects with a total cost less than \$300,000. Contractors that are currently Prequalified may be placed on the Small Works Roster by completing the Small Works Roster Supplement located on the Contract Ad & Award website. For contractors who are not currently prequalified, application for prequalification for small works roster shall be submitted on DOT Form 420-020 (Small Works Questionnaire). Both forms are available by emailing prequal@wsdot.wa.gov or can be printed from the WSDOT Contract Ad & Award website at: <http://www.wsdot.wa.gov/biz/contaa/prequal/default.htm> Applications for placement on the Department of Transportation Small Works Roster will be accepted by emailing prequal@wsdot.wa.gov

Title VI Notice to Public

It is the Washington State Department of Transportation's (WSDOT) policy to assure that no person shall, on the grounds of race, color, national origin or sex, as provided by Title VI of the Civil Rights Act of 1964, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities. Any person who believes his/her Title VI protection has been violated, may file a complaint with WSDOT's Office of Equal Opportunity (OEO). For additional information regarding Title VI complaint procedures and/or information regarding our non-discrimination obligations, please contact OEO's Title VI Coordinator Oscar Cerda at (360) 705-7082.

Americans with Disabilities Act (ADA) Information: This material can be made available in an alternate format by emailing the WSDOT Diversity/ADA Affairs team at wsdotada@wsdot.wa.gov or by calling toll free, 855-362-4ADA(4232). Persons who are deaf or hard of hearing may make a request by calling the Washington State Relay at 711.

BID OPENING WEDNESDAY, NOVEMBER 15, 2017

- *1. (SKAGIT) **GRIBBLE CREEK FISH PASSAGE** (CL 1 or 6, \$1,500,000 - \$2,000,000) **CONTAINS VOLUNTARY MSVWBE GOAL: 26%**. A State Project on SR 9, MP 47.95 to MP 48.05. Requires: Installing a box culvert, grading stream realignment, HMA paving, pavement marking, guardrail, erosion control, planting, traffic control and other work. 93 Working days. Involves 95 items. 4880 T gravel borrow incl haul, 4060 CY embank comp, 3610 CY channel excav incl haul, 1350 T streambed cobbles, 340 T streambed boulder, 21 EA large woody material, 2200 CY struct excav CL A incl haul, 700 CY gravel backfill, 132 LF bridge rail, 136 LF traffic barrier, 1920 T permeable ballast, 430 SY plane bit pvmt, 250 T HMA CL 1/2 IN PG 64-22, 2467 LF compost sock, 57 EA western red cedar, 262 EA vine maple, 296 EA black twinberry, 344 EA red osier dogwood, 693 EA western sword fern, 532 EA sitka willow, 500 EA slough sledge, 450 EA soft rush, 315 EA fascines, 1 ACRE soil amend, 1 ACRE bark or wood chip mulch, 600 SQ biodegradable erosion control blanket, 75 LF beam guardrail, 640 LF wire fence, 380 SY const geotextile. **CONTAINS MINIMUM BID ITEM TYPE B PROGRESS SCH.** Lump Sum Bids for: Precast reinf split box culvert, temp stream diversion, shoring or extra excav CL A, erosion control and water pollution prevent, herbicide application prior to clearing, temp dewatering plan, temp dewatering sys, perm signing, temp traffic control, struct survey, rdwy survey, relocate gate, SPCC plan. (XL-5029)(100937H)(17A019)(9167)(4 of 4)(1)
- *2. (WALLA WALLA) **0.2 TO 1.8 MILES N OF OREGON BORDER ROCKFALL PREVENTION** (CL 39, \$2,500,000 - \$3,000,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 3%**. F.A. No. STPF-0730(004) on US 730, MP 0.04 to MP 1.93. Requires: Constructing 16 slope fences for rock fall prevention, traffic control and other work. 140 Working days. Involves 10 items. 4914 LF flex rockfall fence. Lump Sum Bids for: Temp traffic control, SPCC plan. (XL-5076)(573001D)(17Y010)(9163)(6 of 4)(6)(2)

BID OPENING WEDNESDAY, NOVEMBER 29, 2017

- *1. (KING) **GEORGE WASHINGTON BRIDGE PAINTING (STAGE 2) & PAVING** (CL 8, Under \$30,000,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 3%**. F.A. No. NHPP-0099(137) on SR 99, MP 34.17 to MP 34.73. Requires: Cleaning and painting the metal surfaces of the truss, top and lower laterals, sway frame, and bearings, removing and replacing the existing HMA paving and membrane on the bridge deck, performing deck repair, repairing finger joint, cleaning sliding plate expansion joints, installing containment systems, installing temporary erosion control measures and temporary navigational lighting system, traffic control and other work. 391 working days. Involves 59 items. 513 LF expansion jnt mod, 835 SF bridge deck repair, 18717 SY waterproof membrane, 800 LF clean/seal/caulk pack rust, 4331 LF safety cable, 538 SF maintenance platform, 18717 SY remove exist overlay from bridge deck, 139 SY plane bit pvmt, 1940 T HMA CL 3/8 IN PG 64-22, 4503 LF paved panel joint seal, 80 day ESC lead, 152 EA barrier delineator, 2980 LF paint line, 11920 LF profiled plastic line, 14900 LF temp pvmt marking long duration, 896 HR flaggers, 1140 HR other traffic control labor, 21 EA schedule update, 2000 HR training. **CONTAINS MINIMUM BIDS ITEMS: TYPE C PROGRESS SCH, SCH UPDATE.** Lump Sum Bids for: Expansion jnt mod, finger joint, clean & paint bridge, containment of abrasives, illum system, temp traffic control, pedestrian traffic control, struct survey, SPCC plan, health & safety plan, air monitoring, reference exist pvmt markings. (XL-5208)(109946C)(17A015)(9168)(5 of 6)
- *2. (JEFFERSON) **W OF 4 CORNERS RD TO E OF WATER ST PAVING AND ADA COMPLIANCE** (CL 4, \$2,500,000 - \$3,000,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 5%**. F.A. No. STBG-0020(192) on SR 20, MP 6.20 to MP 12.54. Requires: Repairing pavement, overlaying, planing and paving with hot mix asphalt, removing surfacing from bridge deck, bridge deck repair and paving, membrane waterproofing, guardrail replacement and adjustment, constructing sidewalks and ramps, installing traffic and pedestrian control systems, pavement markings, pedestrian and traffic control and other work. 55 Working days. Involves 75 items. 91 SY pvmt repair excav incl haul, 92 LF corrugated polyethylene culv pipe, 659 SY waterproof membrane, 30 T CSBC, 6 MI shoulder finish, 34240 SY plane bit pvmt, 12606 T HMA CL 1/2 IN PG 64-22, 172 T commercial HMA, 52 LF HMA sawcut and seal, 11 SY seed, fert by hand, 204 LF cement conc traffic curb and gutter, 179 LF cement conc pedestrian curb, 1906 LF extruded curb, 2826 LF beam guardrail, 150 LF guardrail buried term, 3056 LF raise exist beam guardrail, 71510 LF paint line, 4974 LF grooved plastic line, 24930 LF plastic wide lane line, 2540 SF plastic crosswalk line, 61 EA plastic traffic arrow, 60030 LF temp pvmt marking – short duration, 27 EA

tubular marker, 132 SF detect warning surface, 28 SY access pad, 220 SY cement conc curb ramp. Lump Sum Bids for: Traffic signal sys, temp traffic control, SPCC plan. (XL-5364)(302002B)(17C502)(9171) (4 of 5)(1)

- *3. (KING) **ALASKAN WAY VIADUCT – REPLACEMENT SOUTH ACCESS – SR 99 CONNECTIONS** (CL 1 or 5 & 6, \$20,000,000 - \$25,000,000) **CONTAINS VOLUNTARY MSVWBE GOAL: 26%. A State Project on SR 99, MP 28.87 to MP 34.17. CONTAINS APPRENTICE UTILIZATION REQUIREMENT: 15%.** Requires: Grading, constructing storm drainage systems, fire protection system, bridge approaches for Bridge 99/539N-N, retaining walls, paving with HMA and PCCP, installing concrete barriers, curbing, pavement markings, permanent signing, traffic signal systems, illumination systems, erosion and water pollution control, landscape, traffic control and other work. 260 working days. Involves 289 items. 12370 CY rdwy excav incl haul, 23730 T gravel borrow incl haul, 2580 T mineral aggregate, 11710 CY embank comp, 5830 CY EPS geofoam lightweight fill, 550 CY landscape EPS geofoam lightweight fill, 24340 T dispose contaminated material, 42 EA catch basin, 3813 LF test storm sewer pipe, 1684 LF TV inspection, 1833 LF sch A storm sewer pipe, 1988 LF ductile iron storm sewer pipe, 1 EA hydrant, 861 CY struct excav CL A incl haul, 62568 LB epoxy-coated st rebar, 93133 LB st rebar, 824 CY conc CL 4000, 1506 LF bridge rail, 452 LF median traffic barrier, 375 LF geofoam wall single slope traffic barrier, 796 LF rdwy slab traffic barrier, 16916 SF conc fascia panel, 265 SY bridge approach slab, 7520 T CSBC, 6155 CY cement conc pvmt, 9040 EA corrosion resist dowel bar, 3491 EA epoxy coated dowel bar, 1822 SY texturing exist cement conc pvmt, 6600 T HMA CL ½ IN PG 64-22, 424 LF irrigation sleeve, 374 LF irrigation casing, 280 DAY ESC lead, 8368 SY topsoil, 164 CY struct soil mix, 962 EA oregon grape, 80 EA excelsa cedar, 23 EA green column black maple, 21 EA new harmony elm, 2 EA Princeton sentry ginko, 2294 EA mt vernon laurel, 9256 EA salal, 3787 EA western sword fern, 8450 SY bark or wood chip mulch, 3920 SF reinforced grass access, 5257 LF cement conc traffic curb, 8 LF beam guardrail, 1730 LF precast conc barrier, 1303 LF single slope conc barrier, 544 LF CIP single slope barrier, 956 LF low profile barrier curb, 696 LF barrier wall, 11360 LF paint line, 26760 LF plastic line, 29460 LF profiled plastic line, 11360 LF profiled plastic wide lane line, 1860 SF plastic crosswalk line, 158 EA plastic traffic letter, 41230 LF temp pvmt marking, 590 LF directional boring, 2020 HR other traffic control labor, 1200 SF const signs CL A, 3210 CY struct excav CL B incl haul, 600 SF fiberglass grating, 17360 SF shoring CL B, 3022 SY cement conc sidewalk, 462 SY asph conc sidewalk, 346 SY cement conc driveway entrance, 15 EA cement conc curb ramp, 1170 LF temp chain link fence, 354 LF pressed point fence, 25 EA tee, 8 EA connect to drain struct, 39 EA adjust manhole, 18 EA manhole, 36 EA adjust valve box, 3 EA adjust exist jct box, 7 EA adjust elect manhole, 14700 SF geosynthetic retaining wall, 1910 CY gravel borrow incl haul, 100 EA no trespassing sign, 1358 SF shotcrete facing. **CONTAINS MINIMUM BID ITEMS: TYPE C PROGRESS SCH, SCH UPDATE.** Lump Sum Bids for: Clean exist drain struct, fire protect sys, placing concrete fascia panel, luminaire foundation mod, bird deterrent, irrigation sys, erosion control and water pollution prevent, portable process water treatment facility, perm signing, sign bridge, illum sys, elect sys mod, traffic signal sys, traffic signal and illum sys, traffic data accum sys, CCTV sys, VMS sys, comm conduit sys, comm cables and interfaces, traffic signal interconnect sys, video, voice & data distribute & trans sys, swing gate sys, temp traffic control, permanent viaduct closure sch, 26KV vent sys, struct survey, rdwy survey, as built survey, ADA features survey, health & safety plan, geotech instrumentation, dewatering sys, just in time training, SPCC plan. (XL-3685) (809936E)(17A805)(9160)(8 of 69)(2)
- *4. (WHATCOM) **SR 9 EAST JUNCTION INTERSECTION IMPROVEMENTS** (CL 4, \$750,000 - \$1,000,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 21%. F.A. No. CBI-0542(045) on SR 542, MP 14.36 to MP 14.73.** Requires: Constructing a roundabout, HMA paving, pavement marking, drainage, electrical, illumination, signing, erosion control, traffic control and other work. 35 working days. Involves 62 items. 332 CY rdwy excav incl haul, 1230 T select borrow incl haul, 176 LF sch A culv pipe, 445 T CSBC, 571 SY texture & pigmented cement conc pvmt, 352 EA corrosion resist dowel bar, 1120 SY plane bit pvmt, 2125 T HMA CL 1/2 IN PG 64-22, 1462 SY soil amend, 1225 LF roundabout cement conc curb & gutter, 229 LF beam guardrail, 2450 LF paint line, 2460 LF grooved plastic line, 5440 LF temp pvmt marking – short duration. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Erosion control & water pollution prevent, perm signing, illum sys, temp traffic control, rdwy survey, SPCC plan.(XL-5290)(154214F)(17A028)(9172)(2 of 3)

BID OPENING WEDNESDAY, DECEMBER 6, 2017

1. (SNOHOMISH) **I-5 INTERCHANGE TO SR 9 PAVING AND ADA COMPLIANCE** (CL 4, \$2,000,000 - \$2,500,000) **CONTAINS VOLUNTARY MSVWBE GOAL: 26%** A State Project on SR 530, MP 17.060 to MP 20.790. Requires: Planing bituminous pavement, paving with HMA, pavement repair, updating curb ramps to ADA standards, signal loop replacement, pavement marking, temporary erosion and water pollution control, traffic control and other work. 65 Working days. Involves 65 items. 820 SY pvmt repair excav incl haul, 100 T CSBC, 74610 SY plane bit pvmt, 8330 T HMA CL ½ IN PG 64-22, 770 LF compost sock, 130 LF cement conc traffic curb, 405 EA flex guidepost, 26430 LF plastic line, 52550 LF profiled plastic line, 1610 LF profiled plastic wide lane line, 860 SF plastic crosswalk line, 3 MI centerline rumble strip, 129060 LF temp pvmt marking – short duration, 260 HR contractor provide uniform police officer, 14 EA adjust monument case & cover, 5 EA cement conc curb ramp. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH** Lump Sum Bids for: Perm signing, traffic signal sys, temp video detect sys, vehicle detect sys, temp traffic control, reference exist pvmt markings, SPCC plan.(XL-5325)(153020E)(17A025)(9179)(1 of 3)

BID OPENING WEDNESDAY, DECEMBER 13, 2017

1. (KING) **SB SR 900 TO COAL CREEK PKWY SE PAVING OUTSIDE LANE** (CL 4, \$1,000,000 - \$1,250,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 16%**. F.A. No. STBG-4053(865) on I-405, MP 4.50 to MP 10.18. Requires: Planing bituminous pavement, paving with HMA, pavement repair, crack sealing, ITS loop replacement, erosion control, temporary and permanent striping, traffic control and other work. 28 Working days. Involves 35 items. 911 SY pvmt repair excav incl haul, 49900 SY plane bit pvmt, 1204 T HMA CL 1/2 IN PG 64-22, 4364 T HMA CL 1/2 IN PG 70-22, 28790 LF plastic line, 29800 LF profiled plastic line, 59600 LF temp pvmt marking- short duration. Lump Sum Bids for: Traffic data accum & ramp meter sys, temp traffic control, rdwy survey, reference exist pvmt markings, SPCC plan. (XL-5322)(140504E)(17A026)(9178)(1 of 4)
2. (SKAGIT) **SHARPES CORNER TO ANACORTES FERRY PAVING & ADA** (CL 4, \$5,000,000 - \$6,000,000) **CONTAINS UDBE CONDITION OF AWARD GOAL: 15%**. F.A. No. NHPP-0020(185) on SR 20 Spur, MP 47.990 to MP 55.400. **CONTAINS APPRENTICE UTILITIZATION REQ: 15%** Requires: Planing bituminous pavement, roadway excavation, paving with HMA, replacing sidewalk ramps, pavement marking, striping, traffic loops, drainage, traffic signal systems, signing, guardrail, concrete barrier, planting, surveying, traffic control and other work. 78 Working days. Involves 83 items. 1924 SY pvmt repair excav incl haul, 123 LF drain pipe, 590 T CSBC, 144590 SY plane bit pvmt, 90 T HMA CL 3/8 IN PG 64-22, 17550 T HMA CL ½ IN PG 64-22, 520 SY sod install, 1467 LF cement conc traffic curb & gutter, 1063 LF cement conc pedestrian curb, 952 LF beam guardrail, 752 LF precast conc barrier, 75320 LF plastic line, 79630 LF profiled plastic line, 10070 LF plastic wide lane line, 35 HUND raised pvmt marker, 260100 LF temp pvmt marking – short duration, 211300 LF temp pvmt marking – long duration, 1500 SF const signs CL A, 597 SY cement conc sidewalk, 51 EA cement conc curb ramp. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH** Lump Sum Bids for: Perm signing, traffic signal sys, temp video detect sys, temp traffic signal sys, temp traffic control, rdwy survey, ADA features survey, reference exist pvmt marking, clean exist drain struct, SPCC plan.(XL-5036)(102029D) (17A007)(9180)(1 of 4)

3. **PRE-BID MEETING**

The Contracting Agency will hold one voluntary pre-Bid meeting for Proposal and Planholders. The meeting will take place on November 30, 2017 at 1:00 p.m. in the Mt. Baker Room at the Mount Baker Area regional headquarters located at 1043 S Goldenrod Rd, Burlington, WA 98233. This meeting will include a safety briefing, a discussion of general requirements, discussion of Minority, Small, Veteran and Women's Business Enterprises (MSVWBE) requirements, partnering, public outreach, construction schedule, construction staging, liquidated damages and incentives. Attendees will be required to sign a waiver, at the meeting. Proposal and Plan holders shall give notice of their intent to attend by phone at (360) 788-7403 or by email at nggabe@wsdot.wa.gov no later than two (2) business days prior to the meeting. Within seven (7) calendar days after the voluntary pre-Bid meeting, the Contracting Agency will post meeting minutes for all Proposal and Plan holders via a Web Posting available for Bidder's inspection at <ftp://ftp.wsdot.wa.gov/Contracts/> organized by Contract Number and Project Title, in the Reference

Information subfolder, and made available for informational purposes only. The meeting is expected to last a total of one hour. All Proposal and Plan holders are encouraged to attend.

(SKAGIT) **SHARPES CORNER VICINITY IMPROVEMENTS** (CL 4, \$5,000,000 - \$7,500,000)
CONTAINS VOLUNTARY MSVWBE GOAL: 26%. A State Project on SR 20, MP 47.04 to MP 48.40.
CONTAINS APPRENTICE UTILIZATION REQ: 15% Requires: Constructing two roundabouts, one at the intersection of SR 20, Miller Rd and Gilbralter Rd., and the other at the intersection of SR 20 and SR 20 Spur, constructing a third lane between the two roundabouts, constructing a pathway between Sharps Corner and Christianson Rd, roadway excavation, embankment compaction, grading, drainage, illumination, concrete curb, gutter, sidewalk, Portland Cement Concrete paving, HMA, paving, pavement marking, permanent signing, erosion and sediment control, planting, traffic control and other work. 95 Working days. Involves 139 items. 14330 CY rdwy excav incl haul, 11100 T select borrow incl haul, 959 CY ditch excav incl haul, 4 EA drop inlet, 287 T streambed cobbles, 1281 T quarry spalls, 652 LF CL V reinf conc culv pipe, 26 EA catch basin, 1990 LF test storm sewer pipe, 2366 LF sch A storm sewer pipe, 9610 T CSBC, 800 T CSTC, 2340 SY textured and pigmented cement conc pvmt, 405 EA corrosion resist dowel bar, 5100 SY plane bit pvmt, 15440 T HMA CL 1/2 IN PG 64-22, 280 T commercial HMA, 4 ACRE seed & mulch, 4720 SY soil decompact, 1467 SY topsoil, 126 EA madrona, 200 EA black twinberry, 174 EA clustered rose, 885 EA creeping oregon grape, 234 EA pacific wax myrtle, 267 EA red flowering currant, 549 EA snowberry, 207 EA thimbleberry, 24640 SY soil amend, 5490 SY bark or wood chip mulch, 3550 LF high vis silt fence, 4741 LF cement conc roundabout curb & gutter, 2703 LF precast dual faced sloped mountable curb, 2195 LF beam guardrail, 236 LF precast conc barrier, 26180 LF grooved plastic line, 3500 LF profiled plastic wide lane line, 2740 LF plastic wide lane line, 3050 SF groove for plastic marking, 1220 SF plastic crosswalk line, 35160 LF temp pvmt marking long-duration, 120 LF direct boring, 315 LF conduit pipe, 3970 CY struct excav CL B incl haul, 23230 SF shoring or extra excav CL B, 32 EA plug exist pipe, 7 EA cement conc curb ramp, 64 SF detect warn surface, 7 EA connect to drain struct, 2560 SY const geotextile. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Erosion control & water pollution prevent, perm signing, temp illum sys, illum sys, traffic signal sys, traffic signal and illum sys, temp video detect, ITS CCTV sys, ITS traffic data accum sys, ITS comm conduit, cables & interfaces sys, ITS video, voice & data dist sys, temp traffic control, rdwy survey, ADA features survey, SPCC plan. (XL-4998)(102029K)(17A020)(9177)(1 of 4)

No projects awarded the week of November 6, 2017.

Roger Millar

Secretary of Transportation

*Previously Advertised **Extended *** Revised