

**NOTICE TO CONTRACTORS
HIGHWAY CONSTRUCTION**

June 18, 2018

Bidding proposals may not be issued to bidders unless they are prequalified, except where otherwise provided in Plans and Specifications. For those contractors who are not prequalified, application for prequalification will be submitted on DOT Form 420-010 (Standard Questionnaire and Financial Statement) and must be received by the Prequalification Analyst no less than fifteen days prior to the scheduled bid opening to receive consideration for issuance of a bidding proposal for that bid opening. Informational copies of plans and specifications are on file in the office of the County Engineer of the County in which the work is situated, the chapter offices of the Associated General Contractors of America, the offices of the Regional Administrators or the Headquarters of the Department of Transportation, and at www.wsdot.wa.gov/biz/contaa/ where they may be inspected. The use of informational proposals shall be allowed only upon written request and will be accepted only when written authority for their use has been granted. **ESTIMATE RANGES PUBLISHED IN THIS NOTICE MUST NOT BE USED AS A BASIS FOR BID PREPARATION.**

All bid proposals shall be accompanied by a bid proposal deposit in cash, certified check, cashier's check or surety bond in an amount equal to five percent (5%) of the amount of such bid proposal. Should the successful bidder fail to enter into a contract and furnish a satisfactory performance bond, the bid proposal deposit shall be forfeited. **Bonds submitted on other than the bond form provided by the department may be subject to rejection. The right is reserved to reject any and all bids and to waive informalities in the bidding.** Sealed bids will be received in the Bid Room 2D20, located on the second floor of the Department of Transportation, 310 Maple Park Avenue SE, Olympia, Washington, 98501 until 11:00:59 am Pacific Time, or at P.O. Box 47360, Olympia, Washington, 98504-7360, until 11:00:59 am Pacific Time or electronically via BidX.com until 11:00:59 am Pacific Time, on the dates shown below except where otherwise provided in the Plans and Specifications.

FEE: Project Documents will be furnished for the non-refundable fee Plus Sales Tax of:

| | | |
|-------------------------------------|--|------------------------------------|
| Electronic – plans only \$10 | Electronic – with proposal \$15 | |
| Paper – one volume \$35 | Paper – two volumes \$50 | Paper – three volumes \$100 |

(Remittance may be made to the Department of Transportation Cash Receipts, Transportation Building, and P.O. Box 47305, Olympia, WA 98504-7305) TO ORDER PLANS AND SPECIFICATIONS PLEASE GO ONLINE TO:

<https://www.wsdot.wa.gov/business/contract-ad-award/order-plans>

Electronic Project Plans, Specifications, Geotechnical Reports, Addenda, Planholders Lists, Award/Bid Results, and Bid Tabulations are available on the Internet at: <http://www.wsdot.wa.gov/biz/contaa>

SMALL WORKS ROSTER: The Department of Transportation is soliciting contractors interested in qualifying for placement on the department's Small Works Roster. The small works roster process as authorized by RCW 39.04.155 and WAC 468-15 may be used to secure bids for the Agency's small works projects with a total cost less than \$300,000. Contractors that are currently Prequalified may be placed on the Small Works Roster by completing the Small Works Roster Supplement located on the Contract Ad & Award website. For contractors who are not currently prequalified, application for prequalification for small works roster shall be submitted on DOT Form 420-020 (Small Works Questionnaire). Both forms are available by emailing prequal@wsdot.wa.gov or can be printed from the WSDOT Contract Ad & Award website at: <http://www.wsdot.wa.gov/biz/contaa/prequal/default.htm> Applications for placement on the Department of Transportation Small Works Roster will be accepted by emailing prequal@wsdot.wa.gov

Title VI Notice to Public

It is the Washington State Department of Transportation's (WSDOT) policy to assure that no person shall, on the grounds of race, color, national origin or sex, as provided by Title VI of the Civil Rights Act of 1964, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities. Any person who believes his/her Title VI protection has been violated, may file a complaint with WSDOT's Office of Equal Opportunity (OEO). For additional information regarding Title VI complaint procedures and/or information regarding our non-discrimination obligations, please contact OEO's Title VI Coordinator Larry Watkinson at (360) 705-7090.

Americans with Disabilities Act (ADA) Information: This material can be made available in an alternate format by emailing the WSDOT Diversity/ADA Affairs team at wsdotada@wsdot.wa.gov or by calling toll free, 855-362-4ADA(4232). Persons who are deaf or hard of hearing may make a request by calling the Washington State Relay at 711.

BID OPENING WEDNESDAY, JUNE 27, 2018

- *1. (CLARK) **BRUSH PRAIRIE RR XING BUS AND TRUCK PULLOUT LANES** (CL 1 & 2 or 4, \$500,000 - \$600,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 11% F.A.** No. HSIP-0503(034) on SR 503, MP 4.33 to MP 4.67. Requires: Excavating roadway, paving with HMA, illumination system removal and replacement, restoring pavement marking, traffic control and other work. 25 Working days. Involves 32 items. 1300 CY rdwy excav incl haul, 1600 T CSBC, 1400 T HMA CL 3/8 IN PG 58H-22, 1290 SY seed, fert, mulch, 1720 LF high vis fence, 6245 LF plastic line, 6 EA plastic RR crossing symbol, 3350 LF temp pvmt marking-short duration, 184 SF const sign CL A. Lump Sum Bids for: Perm signing, illum sys remove and replace, traffic signal sys loop replace, temp traffic control, SPCC plan. (XL-5264)(450318R)(18X318)(9291)(3 of 3)4(1)

BID OPENING WEDNESDAY, JULY 11, 2018

- *1. (SNOHOMISH) **MUKILTEO FERRY TERMINAL (PHASE 2) FERRY TERMINAL CONSTRUCTION** (CL 1 & 6 or CL 6 & 49 or CL 7, \$50,000,000-\$60,000,000) **CONTAINS: CONDITION OF AWARD DBE GOAL: 6%.** CMAQ-WA-2017-016, CFDA 20507, TIGER-WA-2017-007, CFDA 20933 PSRC-WA-2017-023, CFDA 20507 on SR 525 for Washington State Ferries. **CONTAINS APPRENTICE UTILIZATION REQ: 15%.** Requires: Construction of ferry terminal including building, toll booths, fishing pier, overhead loading, berthing structures, steel piling, concrete work, retaining walls, paving, utilities, landscaping, demolition of existing ferry terminal facility, traffic control and other work. 525 Working days. Involves 411 items. 2080 LF abandon water line, fill with CDF, 6740 LF remove below grade liquid gas piping, 4949 CY rdwy excav incl haul, 48282 T gravel borrow incl haul, 26095 CY embank comp, 4863 T sand, 148 EA streambed boulder, 1640 LF underdrain pipe, 74366 SF impermeable layer, 4007 LF test storm sewer pipe, 4007 LF sch A storm sewer pipe, 8 EA mod wetlands, 16 EA elastomeric tidal check valve, 1730 LF PVC sanitary sewer pipe, 14 EA hydrant assembly, 4260 LF ductile iron pipe, 27 EA gate valve, 870 LF conc trench, 3821 CY struct excav CL A incl haul, 653 LF shaft, 646 LF furnish soldier pile, 4139 LF furnish st pile, 116 EA drive st pile, 1100 LF sew traffic barrier, 37348 LB epoxy-coated st rebar, 58560 LB st rebar, 3 EA QA shaft test, 945 CY conc CL 4000, 1180 SF lagging, 1500 SF conc fascia panel, 23590 SF struct earth wall, 157 EA furnish st pile tip or shoe, 4210 LF furnish st pile, 41 EA drive st pile, 10 MBM timber and lumber acza treated, 17 EA marine fender, 394 LF construct shaft, 1604 LF railing, 8 EA floating dolphin anchor, 2750 LF floating dolphin anchor chain, 5950 T gravel base, 6227 T CSBC, 2164 T pervious base pvmt, 1688 CY pervious conc pvmt, 436 SY seeded aggregate cement conc sidewalk, 12205 T HMA CL 1/2 IN PG 64-22, 240 DAY ESC lead, 17518 EA PSPIPE items, 4435 ACRE topsoil, 306 LF conc seat wall, 11623 LF cement conc traffic curb and gutter, 11484 SF green bike lane marking, 10782 CY struc excav CL B incl haul, 52248 SF shoring or extra excav 2178 CY gravel backfill, 5907 SY cement conc sidewalk, 6232 SF gravity block wall, 20 EA manhole, 11037 F geosynthetic retaining wall, 11413 CY gravel borrow incl haul, 1387 CY bioretention soil mix, 3 EA toll booth. **CONTAINS MANDATORY BID AMOUNT: TYPE C PROGRESS SCH & SCH UPDATE.** Lump Sum Bids for: VTS sewer sys, HDPE SS FM SUSP fr trestle w/ hanger & insul, magnetic flow meter vault, vts water supply sys, dcda with vault & drain, RPBA with hot box, FDC and PIV, bridge deck OHL transfer span, struct st OHL transfer span, struct st wingwalls, struct st dolphins, struct low alloy st Mukilteo TRM transfer span, chain & hardware wingwalls, chain & hardware dolphins, UHMW polyethylene rubbing face, apply pigmented sealer to exist conc surface, relocate & anchor exist floating dolphin, irrigation sys, environmental compliance lead, perm signing, temp traffic control, illum sys, marine survey, bird deterrent sys, VTS hydraulic sys, VTS hydraulic cylinders, VTS hydraulic power units, VTS pins & bearings, VTS elec sys, VTS mechanical & controls integration, struct survey, rdwy survey, ADA features survey, protected species monitor, general elec, OHL architecture and elec, passenger overhead loading sys, security sys, signage & wayfinding, weather station, terminal bldg. roof antenna, VMS signs, great hall transit seating, field office bldg, contractor survey bioretention fac & features, ferry terminal bldg, maint bldg, toll booth canopy, SPCC plan. **ALTERNATE A:** Construct fishing pier. **ALTERNATE B:** Demolition of existing ferry terminal marine work portion. (XL-4681)(904433A)(14W121)(9244)(8 of 6)10(2)
2. (CLARK) **I-205 RAMP METER AND SR 503 VARIABLE MESSAGE SIGN** (CL 41, \$500,000 - \$600,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 5%.** F.A. No. CMAQ-0503(037) on I-205, MP 30.80 to MP 31.45 and SR 503, MP 1.20 to MP 1.40. Requires: Furnishing and installing a ramp metering system, cantilever sign structure, Variable Message Sign, illumination, Intelligent Transportation System, permanent signing, erosion control, traffic control and other work. 40 Working days. Involves 26

items. 1635 LF high vis fence. Lump Sum Bids for: Perm signing, cantilever sign struct, CCTV sys, ITS comm conduit sys, ITS comm cables & interfaces, ITS traffic data accum & ramp meter sys, ITS VMS, video/data trans & dist sys, illum, elec sys install & mod, temp traffic control, SPCC plan. (QL-0099)(400019R)(18X316)(9293)(1 of 3)

3. (CHELAN & GRANT) **NCR ADA COMPLIANCE 2018** (CL 17, \$400,000 - \$500,000) **CONTAINS VOLUNTARY SMALL BUSINESS ENTERPRISE GOAL: 10%**. F.A. No. STPF-9999(749) on US 2, MP 81.72 to MP 81.93, MP 99.04 to MP 100.70 and I-90, MP 161.27 to MP 161.89. Requires: Removing pavement markings, roadway excavation, crushed surfacing, commercial HMA, cement concrete curb and gutter, traffic curb and pedestrian curb, illumination system, ADA features survey, cement concrete sidewalk and curb ramps, pedestrian traffic control, traffic control and other work. 30 Working days. Involves 38 items. 187 T crushed surface top course, 46 T commercial HMA, 12 EA inlet protection, 704 LF cement conc traffic curb and gutter, 197 LF cement conc traffic curb, 460 LF cement conc pedestrian curb, 236 SF const signs CL A, 211 SY cement conc sidewalk, 22 SY paver stone sidewalk, 444 SY cement conc curb ramp. Lump Sum Bids for: Illum sys, traffic signal sys, temp traffic control, pedestrian traffic control, ADA features survey, SPCC plan. (XL-5010)(200207L)(18B013)(9295)(1 of 3)
4. (MASON) **LYNCH ROAD INTERSECTION SAFETY IMPROVEMENTS** (CL 4, \$1,250,000 - \$1,500,000) A State Project on US 101, MP 351.61 to MP 353.19. **CONTAINS VOLUNTARY MSVWBE GOAL: 26%**. Requires: Surfacing, planing bituminous pavement, hot mix asphalt paving, shoulder finishing, TESC, drainage, erosion control, delineation, guardrail, high-tension cable barrier system (4 cable), signing, illumination, traffic control and other work. 25 working days. Involves 53 items. 2560 T select borrow incl haul, 6 EA catch basin, 2720 T CSBC, 1960 SY plane bit pvmt, 4050 T HMA CL 1/2 IN PG 58H-22, 1310 SY compost amended vegetated filter strip, 1663 LF beam guardrail, 4380 LF high-tension cable barrier 4 cable sys, 2800 LF paint line, 4790 LF grooved plastic line, 3770 LF grooved plastic wide lane line, 26 EA plastic jct box marking, 10000 LF temp pvmt marking-short duration, 23 CY struct excav CL B incl haul. Lump Sum Bids for: Additional high-tension cable barrier components, illum sys, temp traffic control, SPCC plan. (XL-5852)(310103G)(18C524)(9294)(1 of 3)
5. (CLARK) **DRAINAGE IMPROVEMENTS** (CL 1, \$500,000 - \$600,000) **CONTAINS CONDITION OF AWARD UDBE GOAL: 7%**. F.A. No. NHPP-0503(039) on SR 503, MP 1.20 to MP 1.62. Requires: Subgrade improvement, installing storm sewers, surfacing, paving with HMA, installing pavement markings, signing, traffic control and other work. 20 Working days. Involves 68 items. 1802 CY pond excav incl haul, 1 EA conc inlet, 7 EA catch basin, 381 LF test storm sewer pipe, 267 LF CL V reinf conc storm sewer pipe, 1 EA stormwater pre-treatment struct, 66 LF ductile iron sewer pipe, 850 SY plane bit pvmt, 213 T HMA for pvmt repair, 225 SY stabilized const entrance, 728 SY biodegradable erosion control blanket, 360 LF cement conc traffic curb and gutter, 2440 LF plastic line, 164 SF const signs CL A, 156 CY struct excav CL B incl haul, 77 CY controlled density fill, 186 SY cement conc sidewalk, 585 LF chain link fence. Lump Sum Bids for: Temp traffic control, pedestrian traffic control, ADA features survey, SPCC plan. (XL-5525)(450319D)(18X332)(9292)(1 of 3)

Projects awarded the week of June 4, 2018

(Lewis, Yakima, Benton, Franklin, Walla Walla, Columbia, Garfield, Asotin) SCR 17-19 Region Wide Rumble Strips - #9281 – Construction Ahead, Inc., dba Pavement Surface Control, Kennewick, WA 99336-5604 - \$572,720.05

Roger Millar

Secretary of Transportation

*Previously Advertised **Extended *** Revised