

Interim GSPs**Published after November 20, 2023 GSP Official Update Package**

The following is a list of GSPs that were modified after the November 20, 2023 update package.

Only changes resulting in a new GSP date are included in this list. Any minor changes to fix formatting or spelling errors that did not result in a date change are not included.

To view all GSPs, please visit our website:

GSP	Effective Date	Change
1-06.OPT2(A).GR1	12/20/2023	Updated Buy America/Build America language
1-07.9(1).OPT1.GR1	1/10/2024	Updated Federal Wages to 2024
1-07.9(1).OPT2.FR1	1/10/2024	Updated Federal Wages to 2024
1-07.9(1).OPT5.FR1	1/10/2024	Updated Federal Wages to 2024
1-07.9(1).OPT6.FR1	1/10/2024	Updated Federal Wages to 2024
1-07.11(2).OPT1.2025.GR1	1/24/2024	Added RCW 49.60.530 nondiscrimination language
1-08.1(9)B.OPT1.2025.GR1	1/24/2024	Added RCW 49.60.530 nondiscrimination language to subcontracts.
1-09.2(1)A.OPT1.GR1	1/24/2024	Added the WSDOT Portal requirements for HMA tickets
1-09.2(1)A.OPT2.GR1	1/24/2024	Added the WSDOT Portal requirements for all tickets
1-09.2(6).OPT1.GR1	1/24/2024	Added the WSDOT Portal requirements for HMA tickets
1-09.2(6).OPT2.GR1	1/24/2024	Added the WSDOT Portal requirements for all tickets
1-03.3.OPT2.GR1	2/13/2024	Updated email and physical address for delivery of Trucking forms.
1-07.1.OPT3.FR1 renamed to 1-07.1(2).OPT1.FR1	2/13/2024	Moved and renamed the confined space GSP to be under Health and Safety heading. No date change.
1-08.1(7)C.OPT1.2025.GR1	2/13/2024	Fixed error in the reference to 1-08.1(10).
1-10.3(3)A.OPT1.2025.GR1	2/13/2024	Allows an alternate method for covering signs when they will be covered for 7 calendar days or less.
6-05.3.OPT1.FB6 (Index only)	2/13/2024	Fixed errors in index instructions for use. No Date change.
6-15.3(8).OPT1.2025.GR6	2/13/2024	Modified the location for the maximum test load.
6-17.3(8).OPT1.2025.GR6	2/13/2024	Modified the location for the maximum test load.
6-19.3(7)F.OPT1.2025.GR6	2/13/2024	Allows crosshole sonic log testing to be done either before or after preparing the shaft construction joint.
6-21.SA1.2025.GR6	2/13/2024	Adds in Section 6-21.2 - Materials , which was left out of the 2024 Standard Specifications in error.
8-01.2(9-14.6(4)A).OPT1.2025.GR8	2/13/2024	Removes wattles from use as materials for check dams.
8-01.3(6).OPT1.2025.GR8	2/13/2024	Removes wattles from use as materials for check dams.
8-30.3(2).OPT1.FR8	2/13/2024	New GSP for adding in propotions for Streambed Aggregates.
STDPLANS.GR9	2/13/2024	Added in changes to C-60.10 and C-85.11
6-10.3(5).OPT1.GR6	2/26/2024	Added language to index instructions to require HQ Construction approval to require F shape for more than 1000 LF of temporary barrier. No Date change.
6-10.3(5).OPT2.2025.GR6	2/26/2024	New GSP to clarify that Type 2 precast and steel barrier can be used as temporary barrier.
STDPLANS.GR9	2/26/2024	Added in changes to C-60.10 to allow lifting holes and to C-85.11 to allow polystyrene or polyethylene foam.